

## FRENCH ROCKS DIVISION.

*The 20th January 1898.*

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 10th February 1898, for completing the restoration of the Devaroy Anikat across the Cauvery River in the Seringapatam taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of November 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 9-30 A. M. and 5-30 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 1,000 (one thousand) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for completing the restoration of Devaroy Anikat," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

<i>Items of work.</i>	<i>Per.</i>	<i>Quantity.</i>
Dismantling and removing the old apron sicut with jelly mixed with clay, &c.	C. yds.	2,175
Re-filling with the above stuff as packing	S. ft.	1,355
Benching rock	S. ft.	4,535
Blasting rock	C. yds.	4
Excavating soft rock		50
Stone in surki including barging and carting 3 miles lead	C. ft.	17,978
Hammer dressed stone in surki mortar including barging, carting, &c.	"	9,381
Surki concrete	"	16,116
Cement pointing	Sqr.	114-62
Burnt stone slabs set in surki	C. ft.	386
Baling water including ring bund, &c.		Lump sum.

*The 14th January 1898.*

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, French Rocks division, up to 15th February 1898, for constructing a new Munsiff's Court at Seringapatam. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1898.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at French Rocks between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tenders for constructing Munsiff's Court at Seringapatam," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Description of work.	Unit of work.	Rate per unit.
Excavation	C. yds.	177
Earthwork filling	Do	84
Stone in mortar	C. ft.	4,210
Brick in mortar	Do	10,082
Do circular arch work	Do	182
Do flat arch work	Do	175
Burnt stone slabs for lintels	S. ft.	73
Do dressed	Do	237
Plastering with mortar	Sqr.	136.00
White washing (two coats)	Do	74.59
Colar washing do	Do	61.41
Flooring with chunam concrete including smoothening over 4" thick.	Do	18.14
Flooring with asphalt 1" thick	Do	3.78
Do with stone flagging	Do	6.58
Teak wood wrought and put up	C. ft.	394.32
Roofing with Mangalore flat tiles with teak reapers 1" x 1 1/2" including chunam holders, &c., complete.	S. qr.	79
Ridging with Mangalore ridge tiles fixed in mortar	R. ft.	30 1/2
Terracing pucks with brick on edge, &c., (9" thick)	Sqr.	23.09
Cornice ordinary with dental cornice below	R. ft.	124
Do parapet walls with double courses of dentals, &c.	Do	189 1/2
Cornice ordinary	Do	230
String course or band at the springing line of arches	Do	38 1/2
Mortar band around the circular ventilator	Do	11
Triangular heads or finials over the buttresses including cornice plastering, &c., complete.	Each	10
Wooden finials ornamental	Do	2
Masonry finials over the gate pillars	Do	2
Coping with brick in mortar including string courses, &c., complete	R. ft.	79
Matting with outer rind of bamboos	Sqr.	18.37
Teak wood door 1/2 battened and 1/2 venetianed, shutters, frames and iron fittings including lock, &c., complete.	S. ft.	126
Teak wood doors with pannelled shutters, frames, iron fittings, &c., complete.	Do	165
Teak wood door with battened shutters, frames, iron fittings, &c., complete	Do	27
Teak wood windows with double 1/2 battened and 1/2 venetianed shutters and glazed shutters including 3/4" iron bars frames and complete.	Do	132
Teak wood window with battened shutters, frames, &c., complete	Do	11
Teak ventilators with frames and iron bars fitted with perforated zinc sheets, &c.	Do	12 1/2
Teak ventilators with frames and glazed shutters, &c., complete	Do	51
Glazed fan lights fixed with frames, &c., complete	Do	11
Window with stained flowered glass shutters with frames, &c., complete	Do	61
Sun shade of teak shingles including rafters, brackets, ornamental eaves board wooden finials, pointing, &c., complete.	Do	22
Ceiling with fine boards to the Court room	Sqr.	5.97
Wood oiling two coats	Do	30.95
Colar painting silicate (two coats)	Do	16.99
Teak eave boards	R. ft.	21
Teak gate shutter including iron fittings, painting, &c., complete	S. ft.	26
Munsiff's seat or dais of teak planks with steps wooden railings as per attached estimate.	Lump sum	
Prisoners dock and witness box	Do	
Levelling the ground and removing rubbish, &c.	Do	
Drainage spout zinc	Do	
CONSTRUCTING DAIS.		
Excavation	C. yd.	1
Brick in mortar	C. ft.	132
Plastering with mortar	Sqr.	63
Teak wood work	C. ft.	6
Teak planking 3/4" thick	S. ft.	156
Railing wooden in front of dais including intermediate and corner parts (moulded).	R. ft.	12